

# Farabaugh Engineering and Testing, Inc.

Project No. T227-02

Report Date: July 15, 2002

Total Pages (inclusive): 24

#### **ASTM 1592**

STANDARD TEST METHOD FOR STRUCTURAL PERFORMANCE OF SHEET METAL ROOF AND SIDING SYSTEMS BY UNIFORM STATIC AIR PRESSURE DIFFERENCE

## TITE-LOC PLUS ALUMINUM ROOF PANEL

16" WIDE / 0.032" THK

FOR

PETERSEN ALUMINUM CORP. 1005 TONNE RD. ELK GROVE VILLAGE, IL 60007

Report Prepared By:

Patrick J. Farabaugh, P.E.

Reviewed and Approved By:

Daniel G. Farabaugh, PE

Project No. T227-02

#### ASTM 1592-01

# STANDARD TEST METHOD FOR STRUCTURAL PERFORMANCE OF SHEET METAL ROOF AND SIDING SYSTEMS BY UNIFORM STATIC AIR PRESSURE DIFFERENCE

### **Purpose**

This test method covers the evaluation of the structural performance of Sheet Metal Panels and Anchor to Panel Attachments for roof or siding systems under uniform static air pressure difference.

## **Test Date**

6-25-02 (3 Spans @ 5' oc.) 6-27-02 (7 Spans @ 2' oc)

## **Test Specimen**

Manufacturer: Petersen Aluminum Corp.

1005 Tonne Rd.

Elk Grove Village, IL 60007

Panel: Tite-Loc Plus ALuminum Roof Panel, 0.032" aluminum, 16" Wide

Clip: Tite-Loc Plus Two Piece Low Floating Clip

Panel Length: as shown

## **Testing Apparatus**

Test Chamber: Vacuum Chamber Composed of Wood

Mounting Frame: Hat Shape Subgirts fastened to W6 X 15 Wide Flange Beams

Pressure Indicator: Digital Pressure Indicators from Micro-Pneumatic Logic, Inc.

Caliper: Mitutoyo Digital Caliper, Model No. CD-12" CP

Project No. T227-02

## **Installation**

- The panels were installed with clips onto 16 ga hat shape subgirts using (2) #12-14 d self drilling fasteners per clip. The side joints were seamed with a mechanical seamer. Continuity fasteners were located at the top of the sidelap joints at panel ends.
- The system was inverted and attached to the steel beams with #14 tek fasteners.
- Plastic (4 mil thick) was employed loosely between the panels and subgirts and in the side joints to create a vacuum seal.

## **Procedure**

- The specimen was checked for proper adjustment and all vents closed in the pressure measuring lines.
- The required deflection measuring apparatus' were installed at their specified locations.
- A nominal initial pressure was applied equal to at least four times but not more than
  ten times the dead weight of the specimen. This nominal pressure was used as the
  reference zero and initial deflection readings were recorded.
- At each load increment, pressure was maintained for a period of not less than 60 seconds and until the deflection gages indicated no further increase in deflections.
- Successive increments were achieved as above until failure or ultimate load was reached.

The test was conducted according to the procedure in ASTM E-1592-01 and as noted herein. In our opinion the tape and plastic had no influence on the results of the test.

Project No. T227-02

THE RESERVE TO SERVE THE PROPERTY OF THE PROPE	TEST DAT	A FOR 16"	TITE-LOC I	PLUS ALU!	M. PANEL	0.032" 3	SPANS @ 5 '-0" oc
	DEFLECT	ON POINT	READINGS	S)			
LOAD (PSF)	D1	D2	D3	D4	D5	D6	REMARKS
· · · · · · · · · · · · · · · · · · ·	and a second of the company of the control of the control	n sa wangan 1 wa 1 was wangan 1 wangan 14 Managan an		······································		an and a state of the state of	
0.5	0	0	0	0	0	0	PANEL WT.
10.9	0.134	1.012	0.154	1.003	0.068	0.921	
0.5	-0.009	0.02	0.002	0.05	-0.002	0.025	PANEL WT.
16.1	0.221	1,364	0.227	1.386	0.077	1.298	The state of the s
0.5	0.013	0.05	0.01	0.098	0.002	0.028	PANEL WT.
21.3	0.312	1.727	0.325	1.767	0.116	1.62	The state of the s
0.5	0.04	0.094	0.023	0.108	0.003	0.029	PANEL WT.
26.5	0.419	2.087	0.44	2.205	0.155	2.034	A STATE OF THE STA
0.5	0.046	0.135	0.032	0.248	0.009	0.096	PANEL WT.
31.7	0.571	2.513	0.579	2.743	0.225	2.336	The state of the s
0.5	0.074	0.054	0.123	0.576	0.011	0.059	PANEL WT.
36.9	0.918	3.213	0.809	3.458	0.372	3.038	
0.5	0.242	-0.427	0.1	1.878	-0.006	-0.487	PANEL WT.
42.1	1.229	3.823	1.201	4.08	0.626	3.636	and the transport of the second secon
0.5	0.412	-0.385	0.139	2.552	-0.001	-0.584	PANEL WT.

ULTIMATE TEST LOAD = 47.3 PSF (PANEL BUCKLING)

NOTE: SEE SKETCH 1 FOR LOCATION OF PANEL BUCKLING.

Project No. T227-02

The state of the s	TEST DAT	A FOR 16"	TITE-LOC	PLUS ALUI	M. PANEL	0.032" 7 5	SPANS @ 2 '-0" oc			
DEFLECTION POINT READINGS (INCHES)										
LOAD (PSF)	D1	D2	D3	D4	D5	D6	REMARKS			
Proposition of the state of the		and an extension of the second								
0.5	0	0	0	0	0	0	PANEL WT.			
10.9	0.037	0.771	0.032	0.747	0.033	0.788	And the said of the support of the said of the spice of the said o			
0.5	0.036	0.032	0.002	0.017	0.007	0.048	PANEL WT.			
16.1	0.073	1.117	0.059	1,125	0.059	1.053	Provided to 1 (1971) **Market A (1979) 1 ** See ground to *1 *4 *1 * September (1779) **			
0.5	0.01	0.028	0.002	0.036	0.012	0.039	PANEL WT.			
21.3	0.09	1.413	0.064	1,362	0.079	1.422	Production of the second secon			
0.5	0.011	0.064	-0.003	0.056	0.028	0.079	PANEL WT.			
31.7	0.265	2.026	0.149	2.013	0.16	2.069	**************************************			
0.5	0,011	0.159	-0.012	0.155	0.01	0.19	PANEL WT.			
42.1	0.311	2.822	0.259	2.77	0.319	2.868	And the first of the transfer of the first o			
0.5	0.019	0.603	0.017	0.741	0.018	0.7	PANEL WT.			
52.6	0.436	3.286	0.398	3.286	0.46	3.354	a promotografia de la colocita de la companio de la companio de la colocita de la colocita de la colocita de l			
0.5	0.037	1.312	0.029	1.246	0.069	1.439	PANEL WT.			
63.0	0.638	3.713	0.559	3.693	0.645	3.702				
0.5	0.123	1.784	0.071	1.722	0.131	1.933	PANEL WT.			
73.4	0.879	4, 126	0.78	4.13	0.878	4.188				
0.5	0.166	2.343	0.148	2.328	0.23	2.548	PANEL WT.			
83.8	1.111	4.576	1.091	4.603	1.226	4.634	t to recommend of the group operation of the ground one Manage group and control of			
0.5	0.318	2.825	0.246	2.854	0.394	3.01	PANEL WT.			
94.2	1,508	5.087	1.494	5.074	1.574	5.092				
0.5	0.418	3.459	0.463	3.431	0.632	3.654	PANEL WT.			
104.6	2.008	5.639	2.022	5.667	2.125	6,11	etit kangana vikko it terifiri kananan armatak mahilitan ya sasioni na mison na na na na na na na maga			
0.5	0.858	4.134	0.817	4.068	0.958	4.33	PANEL WT.			

ULTIMATE TEST LOAD = 114.9 PSF (SIDEJOINT DISENGAGEMENT)

NOTE: SEE SKETCH 2 FOR LOCATION OF SIDEJOINT DISENGAGEMENT.