



Farabaugh Engineering and Testing Inc.

Project No. T128-17

Report Date: February 28, 2017

No. Pages: 10 (inclusive)

PERFORMANCE TEST REPORT

ASTM E330-02 UNIFORM LOAD STRUCTURAL TEST


ON

HIGHLINE SERIES C2 (16" WALL PANEL)



FOR

PETERSEN ALUMINUM CORP.
10551 PAC ROAD
TYLER, TX. 75707

Prepared by:


Paul G. Farabaugh

Approved by:


Daniel G. Farabaugh

Project No. T128-17

Purpose

The purpose of this test is to establish structural loading on the referenced test specimen in accordance with ASTM E-330-02, "Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference" and as provided herein.

Test Completion Date

1/19/17

Test Specimen

Customer: Petersen Aluminum
10551 PAC Rd.
Tyler, TX. 75707

Panel Series: Highline C2 Series

Panel Tested: C2 Wall Panel, 15.356"(coverage) width x 0.032" Alum. or 24 Ga. Steel, with clip end (**HLC2C Panel**) or screw leg end (**HLC2 Panel**).

Panel Clip 20 ga. x 2.5" wide clip

Test Apparatus

A test chamber was used with two static pressure taps located at diagonally opposite corners. A controlled blower provided a uniform pressure load the specimen mock-up. Calibrated manometers were used to measure the pressure at each pressure tap. The uniform load pressure was performed in the negative directions on the panel specimen mock-up. Calibrated deflectometers were attached to monitor panel deformation as shown.

Test Assembly

- The mock-up was 8'-0" wide X 8'-0" high and consisted of a 8 panel wide mock up with 16 ga. horizontal studs spaced at 24" o.c. The specimen was surrounded by a 2 X 12 wood framed perimeter.
- The panels were attached to the 16ga. steel supports using #14 - 13 x 1-1/2" long self drill, flat head, Concealor fasteners. Test #1 & #3 used clip leg with clips using two fasteners per clip and Test #2 & 4 had a screw leg using one screw at each support. The starter panel was also face fastened with (2) 1/4 - 14 x 2" long tek fasteners at each support. The last panel was face fastened with (2) 1/4 - 14 x 2" long tek fasteners. The ends of each panel were fixed to the supports using (1) 1/4-14 x 1-1/2" long tek fastener at the two interior low cells of the panel.
- 4 mil Plastic Sheeting was placed between the structural steel and the exterior metal face panel.
- See attached drawing showing test set-up and assembly details.

Test Procedure

The tests were conducted in accordance with ASTM E-330-02, "Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference" and as provided herein.

Project No. T128-17

ASTM E330 UNIFORM LOAD TEST - NEGATIVE PRESSURE
TEST #1

Panel Tested: **HLC2C Wall Panel**, 16"(nominal) Panel Width x **0.032" Aluminum**

Test Condition: 2 Fasteners per clip at clip leg into supports spaced @ 2' -0" o.c..

LOAD * (PSF)	DEFLECTION READING D-1 (in)
0.6	0.000
11.0	0.177
0.6	0.000
21.4	0.416
0.6	0.003
31.8	0.659
0.6	0.022
42.3	0.942
0.6	0.053
52.7	1.338
0.6	0.123
63.1	1.815
0.6	0.262
73.5	2.432
0.6	0.502
83.9	3.016
0.6	0.826
94.3	3.475
0.6	1.187
104.7	3.763
0.6	1.558
115.1	4.17
0.6	1.692
125.5	4.369
0.6	1.853
135.9	4.595
0.6	2.352
146.3	4.857
0.6	2.817
156.7	5.195
0.6	3.433

RESULTS

During the testing at the pressure 104.7 psf * the center rib buckled

Failure Load = 165.6 psf* . Panel pulled thru at edge (Note - * - Includes panel weight)

Project No. T128-17

ASTM E330 UNIFORM LOAD TEST - NEGATIVE PRESSURE
TEST #2

Panel Tested: **HLC2 Wall Panel**, 16"(nominal) Panel Width x **0.032" Aluminum**

Test Condition: 1 Fastener thru screw leg into supports spaced at 2'- 0" o.c..

LOAD * (PSF)	DEFLECTION READING D-1 (in)
0.6	0.000
11.0	0.164
0.6	0.004
21.4	0.382
0.6	0.015
31.8	1.610
0.6	0.046
42.3	0.880
0.6	0.084
52.7	1.216
0.6	0.155
63.1	1.692
0.6	0.302
73.5	2.295
0.6	0.609
83.9	2.947
0.6	0.865
94.3	3.428
0.6	1.181
104.7	3.865
0.6	1.523

RESULTS

Failure Load = 115.0 psf *. Panel tore around at fastener pullover

(Note - * - Includes panel weight)

Project No. T128-17

ASTM E330 UNIFORM LOAD TEST TEST #3

Panel Tested: **HLC2C Wall Panel**, 16"(nominal) Panel Width x **24 ga. steel**

Test Condition: 2 Fasteners per clip at clip leg into supports spaced @ 2' -0" o.c..

POSITIVE PRESSURE

LOAD (PSF)	DEFLECTION READING D-1 (IN)
0.0	0.000
26.0	0.272
0.0	0.043
52.0	0.469
0.0	0.046
78.1	0.740
0.0	0.084
104.1	0.935
0.0	0.107

NEGATIVE PRESSURE

LOAD * (PSF)	DEFLECTION READING D-1 (IN)
1.2	0.000
27.3	0.396
1.2	0.027
37.7	0.611
1.2	0.041
53.3	0.900
1.2	0.066
63.7	1.185
1.2	0.113
74.1	1.628
1.2	0.477
79.3	1.738
1.2	0.560
105.3	2.222
1.2	0.818

RESULTS

Upon completion of the testing at the **positive pressure** there were no noticeable failures of the specimen.

During the testing at the **negative pressure** at the pressure 74.7 psf* the panel had buckling at center rib @ 4'-0" from panel end. (Note: *- Includes weight of panel)

Project No. T128-17

ASTM E330 UNIFORM LOAD TEST - NEGATIVE PRESSURE
TEST #4

Panel Tested: **HLC2Wall Panel**, 16"(nominal) Panel Width x **24 ga. steel**

Test Condition: 1 Fastener thru screw leg into supports spaced at 2'- 0" o.c..


LOAD * (PSF)	DEFLECTION READING D-1 (in)
1.2	0.000
11.6	0.123
1.2	0.008
22.1	0.278
1.2	0.013
32.5	0.417
1.2	0.019
42.9	0.547
1.2	0.037
53.3	0.784
1.2	0.064
63.7	1.021
1.2	0.094
74.1	1.364
1.2	0.139
84.5	1.824
1.2	0.239
94.9	2.707
1.2	1.065
105.3	3.059
1.2	1.309
115.7	3.339
1.2	1.519
126.1	3.773
1.2	1.845

RESULTS

During the testing at the pressure 89.7 psf* the panel had buckling at center rib.

Failure Load = 165.5 psf* . Panel pull thru at edge. (Note - * - Includes panel weight)


TEST SETUP



PLAN VIEW

CUSTOMER APPROVAL:
 My signature on this print indicates approval of all the information shown (or as amended hereon) and that items made to these specifications will be accepted

NAME: [Signature] (Tina. Angstadt)
 DATE: 4/12/11






Isometric view
 Scale: 1:1

UNITS		METRIC UNITS (mm)	
As Shown	Inches	As Shown	mm
As Shown	Feet	As Shown	mm
As Shown	Meters	As Shown	mm

TOLERANCES UNLESS OTHERWISE NOTED	
As Shown	± .005
As Shown	± .010
As Shown	± .015
As Shown	± .020
As Shown	± .030
As Shown	± .040
As Shown	± .050
As Shown	± .060
As Shown	± .070
As Shown	± .080
As Shown	± .090
As Shown	± .100

THIS DRAWING CONTAINS INFORMATION THAT IS THE PROPERTY OF SFS INC. THE DRAWING MAY NOT BE REPRODUCED, COPIED, OR REPRODUCED, NOR DISTRIBUTED TO THIRD PARTIES WITHOUT WRITTEN CONSENT.



Material: G-90 Galv	Commercial Quality	 P.O. Box 6326 Wyomissing, PA 19810 T. 610.376.5751 F. 610.376.0932	Description: Peterson Horizontal Wall Panel Clip
Material Spec: ---	As Shown Above		Drawing No.: XP-1806 Drawn By: scda Date: 4/15/2011

Project No. T128-17

TENSILE TEST REPORT

Client: Petersen Aluminum
10551 PAC Rd.
Tyler, TX. 75707

Test Date: 3/24/16 & 1/20/17

Test Method: ASTM A370-10 - steel
ASTM B557-10 - aluminum

Material Description:

Sample #0023-17 -HLC2C Wall Panel, 16”(nominal) Width, 0.032" Alum. with clip leg
Sample #0007-17 HLC2 Wall Panel, 16”(nominal) Width, 0.032" Alum. with screw leg
Sample #0016-16 - HLC2C Wall Panel, 16”(nominal)Width, 24 Ga. Steel with clip leg
Sample #0006-17 - HLC2 Wall Panel, 16”(nominal)Width, 24 Ga. Steel with screw leg

Sample No.	Width (in)	Thickness (in)	Yield Load (lb)	Max. Load (lb)	0.2% Offset Yield Strength (psi)	Tensile Strength (psi)	Elongation (% in 2 inches)
0023-17	0.503	0.030	369.2	386.9	24,463	25,642	11.0
0007-17	0.503	0.029	357.2	382.2	24,486	26,200	12.3
0016-16	0.501	0.023	584.5	684.5	50,726	59,433	29.7
0006-17	0.498	0.023	604.1	689.2	52,745	60,167	27.2

Equipment Used: Tensile Machine #QT7-061196-020
Caliper #1074379
Extensometer #10311744D
Micrometer #110596927