



Farabaugh Engineering and Testing Inc.

Project No. T205-21

Report Date: June 29, 2021

No. Pages: 20 pgs (Inclusive)

PERFORMANCE REPORT

ASTM E-283 AIR LEAKAGE TEST

ASTM E-331 WATER PENETRATION TEST

AAMA 501.1 DYNAMIC WATER PENETRATION TEST


ASTM E330 UNIFORM LOAD TEST

ON

MODULARAL METAL PANEL
24" WIDE COVERAGE X 0.050" ALUMINUM

FOR

PETERSEN ALUMINUM CORP.
10551 PAC RD.
TYLER, TX. 75707



Prepared by:

Paul G. Farabaugh

Approved by:

Daniel G. Farabaugh

DANIEL G. FARABAUGH, P.E.
255 Saunders Station Rd
Trafford, PA 15085
412-373-9238



DADE COUNTY
ACCREDITED
LABORATORY



AAMA
ACCREDITED
LABORATORY



TEXAS
ACCREDITED
LABORATORY



FLORIDA
ACCREDITED
LABORATORY & QC ENTITY

Project No. T205-21

AIR LEAKAGE, WATER PENETRATION, DYNAMIC WATER & STRUCTURAL TESTING

Purpose

The purpose of this test is to establish the air, water, dynamic water infiltration rate and structural loads on a 8'-0" wide x 8'-0" high wall system.

Test Date

5-25-21 thru 5-28-21

Test Specimen

Manufacturer: Petersen Aluminum Corp.
10551 Pac Rd.
Tyler, TX. 75707

Test Specimen: ModularAL Metal Panel 24" wide coverage x 0.050" aluminum

Mock-up Size: 96" wide X 96 high (nominal) consisting of 12 panels x 24" wide x various lengths of 0.050" thick aluminum panels.

Mock up -Installation

- The test setup consisted of a 96" wide x 96" high mock-up that used 6" x 16 ga. vertical channel studs spaced at 24" o.c that were attached to the top and bottom horizontal 16 ga. channel track.
- 5/8"thick Densglass Gypsum board was attached to the vertical stud supports using #6 x 1" lg. self -drilling fasteners spaced at 10" o.c.
- The panel support consisted of 16 ga. Zee horizontal supports attached thru the gypsum board and into 16 ga. vertical channel supports using #12 x 1-1/2" long wafer-head self -drilling screws. Additional vertical Zee supports were used at the panel clip locations.

- 1" foam board insulation was between all zee supports and entire mock-up was covered with Ice and Water Shield.
- A 16 ga. lower "J" channel was along the bottom and two sides of the mock-up. The "J" channel had predrilled holes thru the top leg and a #12 -14 x 1-1/2" long wafer-head self-drilling screws spaced at 22" o.c. secured the lower "J" channel thru the gypsum board and into the 16 ga. stud/channel track. The lower "J" channel secured the ends of the foam board and zee supports.
- A starter clip was attached to the Zee support using #12 x 1" lg. wafer-head, self-drilling screws. A minimum of two fasteners per starter clip or 12" o.c. max. spacing per clip based on length of clip.
- The starter panel engaged into a starter clip and was top-fastened with #12 x 1" lg. Stainless Steel Cap head w/EPDM Sealing washer fasteners at the predrilled holes spaced at 8" o.c. max. spacing.
- The vertical edge of the panel had two (2) clips to attach that edge to the 16 ga. vertical Zee supports using (2) #12 x 1" lg. wafer-head, self-drilling screws at each clip.
- A 0.08" aluminum "J" face trim was along the bottom and sides of the mock-up that sat on top of the lower "J" trim. The face trim was secured thru the lower 16 ga. trim and into stud supports with #14 x 3" lg. wafer-head, self-drilling screw spaced at 24" o.c..
- See installation details for location of fasteners at supports and attachment of each panel.

Test Procedure

The tests were conducted in accordance with the sections as shown in the following:

- ASTM E 283-04 " Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen",
- ASTM E-331-00," Water Penetration of Exterior Windows, Skylights, Doors and Curtain Walls by Uniform Static Air Pressure Difference"
- AAMA 501.1-05, " Standard Test Method for Exterior Windows, Curtain Walls and Doors for Water Penetration Using Dynamic Pressure."
- ASTM E-330-02, "Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference "

Project No. T205-21

ASTM E-283-04
AIR LEAKAGE TEST

Test Date: 5/25/21

Ambient Temperature = 76 deg. F

Barometric Pressure = 29.98" Hg

POSITIVE PRESSURE
(INFILTRATION)

Static Pressure Differential (psf)	Actual Air Infiltration Rate (cfm/sf)
1.57	0.00
6.24	0.00
15.0	0.00

ASTM E-331-00
WATER PENETRATION TEST

POSITIVE PRESSURE
(INFILTRATION)

Test Date: 5/25/21

STATIC PRESSURE DIFFERENTIAL (PSF)	WATER SPRAY RATE (GAL/HR/SF)	TEST DURATION (MIN)	WATER INFILTRATION
15	5	15	None

Results:

As a result of the test pressure and water spray for the specified time duration, there was no water leakage on the interior side of the specimen.

Project No. T205-21

AAMA 501.1
DYNAMIC WATER TEST

Test Date: 5/28/18

Ambient Temperature = 79 deg. F

Barometric Pressure = 30.16" Hg

POSITIVE PRESSURE
(INFILTRATION)

Test Pressure (psf)	Water Spray Rate (gal/sf/hr)	Time Duration (min)	Comments
15	5	15	No Leakage

Results:

As a result of the test pressure and water spray for the specified time duration, there was no water leakage on the interior side of the specimen.

ASTM E330 UNIFORM LOAD TEST

POSITIVE PRESSURE

Load Pressure (in-h20)	Load Pressure (psf)	Deflection #1 (in)	Deflection #2 (in)	Deflection #3 (in)
0	0.0	0.000	0.000	0.000
3	15.6	0.081	0.259	0.133
0	0.0	0.009	0.014	0.015
6	31.2	0.155	0.418	0.251
0	0.0	0.021	0.027	0.031
9	46.8	0.221	0.546	0.351
0	0.0	0.039	0.076	0.056
0	0.0	0.030	0.040	0.044
12	62.4	0.260	0.617	0.409
0	0.0	0.036	0.047	0.054
15	78.1	0.334	0.762	0.527
0	0.0	0.043	0.059	0.066
18	93.7	0.388	0.927	0.620
0	0.0	0.051	0.085	0.080
21	109.3	0.431	1.015	0.686
0	0.0	0.059	0.103	0.094
24	124.9	0.474	1.095	0.756
0	0.0	0.067	0.120	0.108
27	140.5	0.511	1.165	0.819
0	0.0	0.074	0.139	0.119
30	156.1	0.552	1.246	0.892
0	0.0	0.080	0.159	0.133
33	171.7	0.577	1.297	0.941
0	0.0	0.084	0.173	0.142
38.4	199.8	0.618	1.390	1.026
0	0.0	0.092	0.207	0.160

RESULTS

Upon completion of the testing at the positive pressures noted above there were no noticeable failures of the specimen


NEGATIVE PRESSURE

Load Pressure (in-h20)	Load Pressure (psf)	Deflection #1 (in)	Deflection #2 (in)	Deflection #3 (in)
0	0.0	0.000	0.000	0.000
2	10.4	0.059	0.178	0.068
0	0.0	0.002	0.008	0.003
4	20.8	0.156	0.335	0.168
0	0.0	0.018	0.036	0.019
6	31.2	0.247	0.462	0.250
0	0.0	0.031	0.059	0.028
8	41.6	0.347	0.590	0.339
0	0.0	0.052	0.094	0.046
10	52.0	0.438	0.704	0.419
0	0.0	0.067	0.103	0.062
12	62.4	0.553	0.849	0.539
0	0.0	0.097	0.141	0.088
14	72.9	0.673	0.992	0.647
0	0.0	0.128	0.174	0.113
16	83.3	0.783	1.121	0.745
0	0.0	0.157	0.204	0.136
18	93.7	0.903	1.256	0.836
0	0.0	0.201	0.251	0.169

RESULTS:


Maximum Test Load = 177.3 psf (Seam Disengagement with Zee support fastener pulled out of 16 ga. metal stud supports)


STRUCTURAL TEST SETUP




X# - DEFLECTION
LOCATION


PLAN VIEW








Project No. T205-21














CUSTOMER	EMS-MO	CUSTOMER NO.	-	DIE NO.	032212	REV.
DESCRIPTION	1.250" X 1.250" H CHANNEL	PROPOSAL NO.				
		VB4A3308				


ACTUAL SIZE

ALUMINUM ASSOCIATION STANDARD TOLERANCES			
APPLY UNLESS SPECIFIED OTHERWISE			
UNSPECIFIED: WALL THICKNESS .093			
UNSPECIFIED RADIUS .016			
DIFF. RATING -			
EST.AREA. 334	IN ²	DNW BY NELL	PRESS -
EST.WT. 40.1	LBS/FT.	CDW BY	CAV. -
EST.PER. 7.172	IN	SCALE 3=1	BACK # -
OUT PER -	IN	CODE -	BOL # -
EXPD PER -	IN	DATE 10-28-10 RATIO -	
FACTOR 18		POCKET AREA -	BLADE -
C.C.D.	1.755 IN	ALLOY 6063-T5	DATE SYM
			REVISION
		DIE NO.	052212
		REV.	


sapa:

F. E. T. INC.
Review for general compliance
With test report AS NOTED ONLY
By: PCF
PROJECT # PCF


PRODUCTION DRAWING	
11-12-10	
RELEASED DATE:	
Released By:	<i>William Long</i>
REMOVED BY:	
DESTROY ALL PREVIOUS COPIES	




ADDITIONAL SUPPORT AND TRIM EXTRUSIONS




0.080" ALUM.
STARTER CLIP



0.080" ALUM. "J" FACE TRIM
(TESTING PURPOSES ONLY)



16 GA. ZEE SUPPORT



16 GA. "J" LOWER TRIM
(TESTING PURPOSES ONLY)

Spectrochemical Laboratories-Material Evaluation, Inc.
155 Prominence Drive, New Kensington, PA. 15068
Phone: (724) 334-4140 Fax: (724) 334-4143

Report of Tensile Testing

Date: 28-May-21
Page No.: 1 of 1

Client: Farabaugh Engineering & Testing (Ref. PO #: Verbal - P. Farabaugh)

PIN #	Dimensions (in.)	Area (sq. in.)	Yield Point (lb.)	Tensile Strength (lb.)	Yield	Tensile Strength (psi.)	Elongation (% in 2 in.)	Fracture Location
0.050" Alum.	0.4946 x 0.0481	0.0238	511	544	21500	22900	4.9	M/2 Break

Test Method: Q2300 04 rev.14 (ASTM A370-29, E8-21, or E646-16 : Yld. by 0.2% offset, Elong. after fracture)

Equipment Used: Instron 5900R60HVL (s/n: 1602) w/ Extensometer (s/n: E93054)

Performed By: T. Autl

This test report shall not be reproduced except in full, without the written approval of the laboratory.
The recording of false, fictitious, or fraudulent statements or entries on this report may be punished as a felony under federal law.

Please send your comments and concerns to us at feedback@spectrocheminc.com

For more information call: 724-334-4140

Respectfully submitted,



Todd A. Autl

Laboratory Manager