



## T-250 - OPEN FRAMING SUBSTRATE DETAILS HIP / RIDGE





## NOTES:


1. ALL Z-CLOSURES ARE TO BE SET IN SEALANT AND SEALED UP THE VERTICAL LEG.
2."X" DIMENSION 3/8" SPACING FOR LOW FLOATING SYSTEM TO ACCOMMODATE
UP TO 3" BATT INSULATION, 1" SPACING FOR HIGH FLOATING SYSTEM TO
ACCOMMODATE BATT INSULATION AND/OR THERMAL BLOCK.

SCALE: 3" = 1'-0"

0 1 2 3 4 5 6 in

EFFECTIVE DATE: 01-03-2023

SUBJECT TO CHANGE WITHOUT NOTICE



FLASHINGS

DISCLAIMER: DETAIL SHOWN FOR ILLUSTRATION PURPOSES ONLY. ACTUAL PROJECT DETAIL MAY VARY

## PETERSEN ALUMINUM CORPORATION - PAC-CLAD.COM

F: 903-581-8592

SALES@PETERSENMAIL.COM